

## **Penrith Water Reclamation Plant Report**

Name of wastewater treatment plant	Penrith Water Reclamation Plant

System Summary	Projected					
	2026	2031	2036	2046	2056	
Penrith WRP ADWF (ML/d)	28.8	32.2	35.0	35.5	35.6	
North Richmond load (EP <sub>COD</sub> )	196,423	219,050	237,766	240,952	241,578	

Treatment capacity constraints for 2022 – 2036	Estimated year of exceedance	
Biosolids stabilisation capacity	2025	
Secondary treatment aeration system capacity constraint	2032	
Additional treatment processes are needed for Total Nitrogen compliance under the Hawkesbury Nepean framework.	ince under 2024	

## Summary of servicing strategy for 2022 – 2036

Continue supply of treated effluent to St Mary AWTP, supply to local recycled water customers, and discharge to waterway as per the current EPL. To meet the Total nitrogen compliance under the Hawkesbury Nepean framework, supplemental carbon dosing system needs to be installed before mid-2024.

The Biosolids Dewatering Program funded by the Renewal and Reliability Project. Following this, staged implementation of RO for load compliance across the Yarramundi bubble is needed. Scale of investment is also highly dependent on amount of effluent reused.

Anticipated augmentation and upgrades for 2020 – 2046					
Year commissioned	Description Approximate capital cost (\$M)		Impact on servicing capacity		
2025	Biosolid upgrade- New pre- thickening and recuperative thickening, equipment and upgrade to dewatering and outloading	1.6**	Biosolids capacity upgrade beyond 2036		
2032	Plant-wide upgrade: Staged implementation of RO	30.1	Increased capacity for servicing of growth demand beyond 2030.		

<sup>\*\*-</sup> Project in progress, remaining expenditure to complete

Further investigations				
Alignment of aeration upgrade with bioreactor renewal works under consideration.				
Changes to the Hawkesbury-Nepean load limits may result to additional treatment upgrades.				
Greater Penrith to Eastern Creek growth area under investigation – servicing strategy may impact on demand forecast for				
Penrith WRP.				
Investigations underway to assess FPI, changes on servicing strategy and asset capability – further investment may be required.				

© June 2023 Sydney Water

While Sydney Water has made every effort to provide information that is up to date, this information can be affected by many factors and is provided as a guide only. Sydney Water makes no representation, warranty, undertaking or guarantee (express or implied) that the information provided in this document is accurate, reliable or complete.

Date published: 30 June 2023